## FLARE CTRL RM GENERAL REQUIREMENTS DOCUMENT

10/30/2015

- 1. Accommodate 4 control operators and 8 users.
- 2. Need equipment isolation racks (max qty. 3).
- 3. Provide access from control room to platform.
- 4. Lighting to be 50 FC.
- 5. Location needs access control (card readers).
- 6. Multiple wall mounted view screens for experimental monitoring / LED type flat screens.
- 7. All furniture and equipment racks indicated in concept design are not included in the program requirements and are shown for layout purposes only.
- 8. Mechanical Requirements.
  - $a. \quad Standard\ of fice\ /\ conferencing\ space\ design.$

$$(70^{\circ} + / - 2^{\circ}F, H 50\% + / - 10\%, Min Air Change 2)$$

- b. Heat Load: Assume 8 w/sf. (not including people).
- 9. Fire protection to be wet sprinkler type.
- 10. Floor loading is 250 lb/sf.
- 11. Raised floor is not an air plenum.
- 12. Room shielding is not required for this space.

Michael Kalish	Date	Hantao Ji	Date
Craig Shaw	Date	John Lacenere	Date